

WEST VIRGINIA DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

SPECIAL PROVISION

FOR

STATE PROJECT NUMBER: _____

FEDERAL PROJECT NUMBER: _____

SECTION 401

**HOT-MIX ASPHALT BASE, WEARING, AND PATCHING AND
LEVELING COURSES**

401.10 – PAVING OPERATIONS:

401.10.3 – Spreading and Finishing

ADD THE FOLLOWING SUBSECTION

401.10.3.1 – Paving Lanes: In one day's production, the Contractor shall pave the full width of the roadway without leaving any significant change in elevation along the longitudinal joint between the existing surface or any newly overlaid or milled surface in accordance with Section 401.10.5.

401.10.5 – Joints:

**DELETE THE THIRD PARAGRAPH AND REPLACE WITH THE
FOLLOWING:**

These joints, as well as the transverse joints between one day's production and the next shall be carefully constructed and shall be formed by cutting back into the existing section to expose the full depth of the course. All joints shall be squared up to the full vertical depth of the course to be placed, and a tack coat of asphalt material shall be applied. Joints adjacent to curbs, gutters, or adjoining pavement shall be formed by transporting back sufficient hot material to fill any space left uncovered by the paver. The joint shall be set up to a sufficient height to receive the full compactive effort from the rollers.