

WEST VIRGINIA DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

SPECIAL PROVISION

FOR

**STATE PROJECT NO.
FEDERAL PROJECT NO.
FOR**

**SECTION 638
PROJECT MARKERS, RIGHT-OF-WAY MARKERS,
AND SURVEY MARKERS**

DELETE THE HEADING AND REPLACE WITH THE FOLLOWING:

**SECTION 638
PROJECT MARKERS, RIGHT-OF-WAY MARKERS,
SURVEY MARKERS, AND OUTLET MARKERS**

638.1-DESCRIPTION:

DELETE THE FIRST PARAGRAPH AND REPLACE WITH THE FOLLOWING:

This work shall consist of furnishing, and placing or installing at the points designated on the Plans, in the Contractor's Proposal or by the Engineer, metal (signpost) project markers, right-of-way markers, concrete survey markers, and outlet markers in accordance with these Specifications and in reasonably close conformity to the lines, grades, dimensions, locations, and sections shown on the Plans, in the Contractor's Proposal or established by the Engineer.

638.2-MATERIALS:

ADD THE FOLLOWING AS THE THIRD PARAGRAPH:

The materials for Outlet Marker Signs, such as for the sign panels, their supports, and for the legend and background, are to be of a type and method of fabrication that will be consistent with the conditions and estimated period of use. Signs shall have black letters for the legend on a white background. Reflective sheeting will be permitted, but not required.

DELETE SUB-SECTIONS 638.6, 638.7, AND 638.8 AND REPLACE WITH THE FOLLOWING:

638.6-OUTLET MARKERS:

638.6.1-General:

Outlet Markers Signs shall be furnished by the Contractor and placed during the mobilization of the project. The Outlet Marker Sign shall be in accordance with the drawing on page 3 and placed at a minimum of three (3) feet above the existing ground level. The Outlet Marker Signs shall become the property of the Division and remain in place upon completion of the project unless otherwise directed by the Engineer.

638.6.2-Location And Content:

The Outlet Marker Signs for projects shall be placed at each discharge point as indicated in the Special Provision for NPDES PERMITS contained within the Contractor's Proposal and conform to the example as shown on the attached drawing.

The following information shall be placed on the Outlet Marker Signs:

1. WVDOT-DOH
2. NPDES Registration Number
3. Outlet Number

638.6.3-Installation:

Mounting, transverse location, and similar features for Outlet Marker Signs shall be consistent with practices used for the installation of other informational signs either on wooden or steel U-channel supports to comply with small sign support safety practices. The sign shall be mounted as directed by the Engineer.

638.7-METHOD OF MEASUREMENT:

The quantity of work done will be the actual number of "Project Markers", "Right-of-Way Markers", "Survey Markers" or "Outlet Markers", complete in place and accepted.

638.8-BASIS OF PAYMENT:

The quantities, determined as provided above, will be paid for at the contract unit prices bid for the items listed below, which prices and payments shall be full compensation for excavating, backfilling, disposing of surplus material, furnishing all the material and doing all the work prescribed in a workmanlike and acceptable manner, including all labor, tools, equipment, supplies, and incidentals necessary to complete the work.

638.9-PAY ITEMS:

ITEM	DESCRIPTION	UNIT
638001-*	PROJECT MARKER	EACH
638002-*	RIGHT-OF-WAY MARKER	EACH
638003-*	SURVEY MARKER	EACH
638004-*	OUTLET MARKER	EACH

*Sequence number

