12-21-2016

BLANKET PERMIT FOR OVERWEIGHT SEAGOING CONTAINERIZED CARGO
SELECTED ROUTES

WV 2
WV 3 - in Boone County & Lincoln County
WV 9
WV 10 – in Lincoln & Logan County
***WV 14 – in Wood County, MP 1.97 to 10.16**
WV 16 – from Dixie in Nicholas County to WV 39 to US 60
WV 16 – from US 19 to US 60 in Fayette Co.
WV 25 – I-64 to Institute
WV 29 WV 127
WV 41 – in Nicholas County
WV 601
WV 55 –Nicholas County from WV 20 to WV 41
WV 55 – in Hardy County from Moorefield to WV 29
WV 61 – from WV 6 to C61/29 in Deepwater
WV 61 – Fayette County from C61/6 in Page to WV 41
WV 75
WV 85 – in Boone County
WV 92 – in Greenbrier Co. from US 60 to Pocahontas Co. Line
WV 94
WV 259 Mercer County to US 460
WV-817
CR 19/19 – in Monongalia County
CR 21 – inWood County, MP 1.97 to 10.16
CR 34 – from Green Valley in Mercer County to US460

WEIGHT AND CLEARANCE RESTRICTIONS

Interstate Routes

I 70 Ohio County – Wheeling Tunnel - No overdimensional loads
I 79 Marion County – MP 136.64 – Southbound overweight loads use left lane.
I 79 Harrison County – MP 115.33 – Southbound overweight loads use left lane.

US Routes and other Routes

C 5 Marshall County – Bridge at MP 3.98 – Restricted to 12 tons
C 74 Marshall County – Bridge at MP 3.72 – Restricted to 29 tons
US 11 Berkeley County – Downtown Martinsburg Railroad Underpass – Restricted to 13' vertical clearance
US 19 Fayette County – MP 7.56 northbound – Restricted to 14' vertical clearance
US 19 Fayette County – MP 26.12 Northbound – Restricted to 36 tons
US 19 Lewis County – MP 6.49 – Restricted to 37 tons
US 19 Monongalia County – MP 6.76 – Restricted to 37 tons
US 19 Nicholas County – MP 8.14 Northbound – Restricted to 40 tons
US 19 Nicholas County – MP 8.14 Southbound – Restricted to 39 tons
US 33 Gilmer County – MP 1.08 – Restricted to 40 tons
US 33 Gilmer County – Stumptown Bridge over Steer Creek – Restricted to 32 tons
US 40 Ohio County – Monument Place Bridge over Wheeling Creek, near Bethlehem - Restricted to 32 tons
US 40 Ohio County – Playground Bridge – Restricted to 40 tons
US 40 Ohio County – Bear Rock Bridge – Restricted to 40 tons
US 40 Ohio County – Lewis Bridge – Restricted to 40 tons
US 40Spur – Ohio County, MP 0.04 – Restricted to 40 tons
US 50 Grant County – Stony River Bridge @ MP 6.19 Restricted to 30 Tons
US 50 Hampshire County – Capon (Truss) Bridge @ MP 31.01 Restricted to 40 Tons
US 50 Harrison County – MP 19.61 Restricted to 37 tons
US 50 Mineral County – New Creek Bridge @ MP 10.65 Restricted to 36 Tons
US 50 Preston County – MP 14.15 – Restricted to 38 tons
US 50 Preston County – Macomber Truss over Cheat River, 2 miles east of Macomber - Restricted to 38 tons and 13' 9" high and all Trucks Go Down Center of Bridge
US 60 Fayette County – MP 0.32 – Restricted to 37 tons
US 119 Roane County – McKown Creek Arch Bridge at milepost 7.49 – Restricted to 40 tons
US 119 Roane County – Lowe Run Arch Bridge at milepost 19.49 – Restricted to 40 tons
US 119 Roane County – Davis Auto Arch Bridge at milepost 19.59 – Restricted to 40 tons
US 119 Roane County – Whiting Electric Arch Bridge at milepost 20.84 – Restricted to 40 tons
US 219 Pocahontas County – Railroad underpass near Mace – Restricted to vertical clearance of 13' 7"
US 219 Randolph County – Hamilton Cobin Bridge at MP 15.02 Restricted to 36 tons
US 220 Grant County – Pansy Bridge @ MP 4.38 Restricted to 36 Tons
US 220 Hardy County – Amby Crites Bridge @ MP 2.44 Restricted to 40 Tons
US 220 Hardy County – Old Town Park Bridge @ MP 11.70 Restricted to 40 Tons
US 220 Hardy County – Mudlick Run Bridge @ MP 17.85 Restricted to 33 Tons
US 220 Pendleton County – Peters Run Bridge at MP 19.27 Restricted to 36 tons
US 250 Barbour County – Philippi Covered Bridge over Tygart Valley River in Philippi - Closed to truck traffic. Use Philippi By-pass.
US 250 Marshall County – Bridge at MP 31.16 Restricted to 33 tons

(Continued on next page)

WEIGHT AND CLEARANCE RESTRICTIONS (continued)

US 250 Marshall County – Park Run Bridge – Restricted to 33 tons
US 250 Randolph County – Cheat Bridge at MP 2.32 – Restricted to 40 tons
WV 2 Marshall County – McDonalds Bridge – Restricted to 40 tons
WV 2 Marshall County – Upper Plaza Bridge – Restricted to 40 tons
WV 2 Ohio County – Short Creek Bridge – Restricted to 40 tons
WV 2 Ohio County – Southbound under I70 in Wheeling – Restricted to 13' 6"
WV 6 Fayette County – MP 0.12 – Restricted to 30 tons and heights of 13’ 6”
WV 7 Monongalia County – MP 27.73 – Restricted to 37 tons
WV 9 Berkeley County – Hedgesville H. S. Bridge @ MP 7.58 Restricted to 40 Tons
WV 9 Morgan County – Sphors X-Road Bridge @ MP 33.30 Restricted to 29 Tons
WV 12 Monroe County – MP 9.25 – Restricted to 40 tons
WV 16 Fayette County – MP 8.68 – Restricted to 36 tons
WV 16 McDowell County – Underpass just north of Welch – Restricted to 12’ 11”
WV 18 Tyler County – Bridge at MP 10.27 – Restricted to 28 tons
WV 20 Harrison County – MP 13.97 – Restricted to 15 tons
WV 20 Harrison County – MP 30.57 (near Dola) – Restricted to 15 tons
WV 20 Nicholas County – MP 13.90 – Restricted to 21 tons
WV 23 Doddridge County – MP 12.34 – Restricted to 36 tons
WV 23 Doddridge County – Travel slowly in the center of all bridges at MP 0.96, 8.20, 12.65, and 15.19
WV 26 Preston County – MP 19.90 – Restricted to 37 tons
WV 28 Hampshire County – MP 22.27 – Restricted to 32 tons
WV 28 Mineral County – Ridgeley Railroad Underpass – Restricted to vertical clearance of 11’ 11”
WV 39 Greenbrier County – MP 6.83 – Restricted to 33 tons
WV 39 Nicholas County – MP 0.08 – Restricted to 13’ 7” vertical clearance
WV 39 Pocahontas County – Buzzard Bridge at MP 27.19 – Restricted to 36 tons
WV 41 Fayette County – MP 0.29 – Restricted to 37 tons
WV 41 Fayette County – MP 5.03 – Restricted to 36 tons
WV 41 Fayette County – MP 6.67 – Restricted to 33 tons
WV 41 Fayette County – MP 7.40 – Restricted to 40 tons
WV 41 Fayette County – MP 20.34 – Restricted to 38 tons
WV 55 Nicholas County – MP 0.55 – Restricted to 40 tons
WV 61 Fayette County – MP 0.04 – Restricted to 40 tons
WV 58 Harrison County – MP 5.53 – Restricted to 34 tons
WV 63 Greenbrier County – MP 21.32 – Restricted to 9’ 9” vertical clearance
WV 63 Greenbrier County – MP 21.36 – Restricted to 30 tons
WV 72 Alternate – Preston County – MP 0.30 – Restricted to 3 tons
WV 82 – Nicholas County – MP 1.30 – Restricted to 33 tons
WV 100 Monongalia County – MP 3.95 – Restricted to 12’ 9” vertical clearance
WV 112 Mercer County – Oakvale to I-77 – Restricted to 10’ 5”
WV 122 Monroe County – MP 11.84 – Restricted to 40 tons
WV 161 McDowell County – RR underpass near Skygusty – Restricted to 13’ 1”
WV 331 Jackson County – entire route restricted to 14 tons
WV 612 Fayette County – MP 0.19 – Restricted to 40 tons
WV 612 Fayette County – MP 0.46 – Restricted to 36 tons